

Airport & English Run Bridge Replacements

Pine Township

Lycoming County

Bassett Engineering Inc.

This project involved the complete demolition, removal and replacement of under-sized, weight limit posted bridges in serious condition. The Project included the replacement of an existing 21' long x 8' wide x 5' high concrete slab bridge with a new 27' long x 10.5' wide x 6' high aluminum box culvert on Airport Road, associated minor stream channel improvements (riprap, rough grading, etc.), and $\pm 290'$ of dirt and gravel roadway restoration. The Project also included the replacement of an existing 14' long x 13.5' wide x 3.5' high steel beam bridge on English Run Road with a new 40.5' long x 15' wide x 6' high aluminum box culvert, associated minor stream channel improvements (riprap, rough grading, etc.), and $\pm 230'$ of dirt and gravel roadway restoration.

This project entailed the replacement of the existing bridges, bank stabilization and roadway safety improvements. Construction was completed in eight weeks.

The projects were built by Wolfe Coal & Excavating, Inc. and Masters Excavating LLC, both located in Loch Haven, PA.

Project Team:
Britt Bassett, PE
Keith Bodwell

Pine Township Supervisors:
Max Harlan
Shelly Johnston
Lori Laubenstein, Secretary
(570) 353-2263

CONSTRUCTION COST:
\$137,800

COMPLETION DATE:
Fall 2015

Airport Road

Before



After



English Run Road

Before



After



Bassett Engineering Inc.

1440 Broad Street
Montoursville, PA 17754

www.bassetteng.com

Phone: 570-368-2131

info@bassetteng.com

Bassett Engineering Inc.